

To: 1 051720 9-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
260, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,649-0000
40' S of
SW NW NE, SEC. 9, T 19 S, R 28 W X E
4250 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name Royalty Well # 1
County Lane 151.25
Well Total Depth 4654 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 9 Year: 1993

Plugging proposal received from Judy

(company name) White & Ellis Drilling (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2118-48'

1st plug at 2140' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:30 p.m. Day: 30 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

If additional description is necessary, use BACK of this form.

1 (did / did not) observe this plugging.

DATE: 10-8-93

INV. NO. 38905

RECEIVED
STATE CORPORATION COMMISSION

OCT 06 1993
10-06-93

Signed Richard M. Lacey (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas