

To: 1 090455 8-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,683-0000
NE NE SW, SEC. 7, T. 7 19 S, R. 28 W,
2310 feet from S section line
2310 feet from WEX section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name H. Thomas Well # 1
County Lane
Well Total Depth 4690 152.43 ft.
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 2:15 p.m. Day: 21 Month: 8 Year: 19 94

Plugging proposal received from Judy
(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

vers: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2147'
1st plug at 2150' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,
3rd plug at 650' with 40 sx cement, 4th plug at 250' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 4:30 p.m. Day: 21 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,
2nd plug at 1320' with 80 sx cement, N
3rd plug at 650' with 40 sx cement,
4th plug at 250' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
8-25-94
AUG 25 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

I (XXXX/ did not) observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 9-6-94
REV. NO. 41116