

1050620

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,186-0000

SE SE NE, SEC. 7, T 19 S, R 28 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Hineman Well # 1

Operator: Bankoff Oil Co.

County Lane 152.10
(Arbuckle)

Name & Address P. O. Box 700657

Well Total Depth 4680 feet

Tulsa, OK 74170

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 397' ✓

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 25 Month: August Year: 19 85

Plugging proposal received from Mike Wagner

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2187'
Anhydrite 2130'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1200' with 70 sx cement

3rd plug 30' out of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 3:00 am Day: 25 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2186' with 50 sx cement, 2nd plug at 1201' with 70 sx
cement, 3rd plug at 428' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(check if not) observe this plugging.

DATE 9-4-85

INV. NO. 9876

RECEIVED Signed R. Lacey
STATE CORPORATION COMMISSION (TECHNICIAN)

9-3-85
SEP 3 1985