

1060137

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101- 20,919-6000

SW SW NE, Sec. 13, T 19 S, R 28 W/4

2310 feet from N/4 section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6390 9067

Lease Name Maughlin Well # 1

Operator: McDonald-Wallace Petroleum
Name & Company, Inc. and DaMar Resources, Inc.
Address P. O. Box 70
Hays, KS 67601

County Lane

Well Total Depth 4650 feet 151.12

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling, Inc. License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 11:30 pm Day: 27 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Larry Booren

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and pump cement through drill pipe.

1st plug at 2000' with 50 sx cement

2nd plug at 1260' with 50 sx cement

3rd plug at 310' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Signed

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:15 pm Day: 27 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement, 2nd plug at 1260' with

50 sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs solid bridge,

hulls - plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate

rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Sun Cementing

RECEIVED
STATE CORPORATION COMMISSION
2-2-84
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed

(TECHNICIAN)

FORM CP-2/3
Rev. 9-82