

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
KANSAS CORP COMM

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

15-1985-00590-0000 (PLEASE TYPE FORM and File ONE Copy)

API # Unk: Compl. 6/22/56 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Ensign Operating Co. KCC LICENSE # 04782 ^{1/00}
(owner/company name) (operator's)

ADDRESS P. O. Box 2161 CITY Liberal

STATE KS. ZIP CODE 67905-2161 CONTACT PHONE # (316) 626-8131

LEASE Potter WELL# 1 SEC. 25 T. 17S R. 25 (~~EAST~~ West)

W/2 - NW - NW - SPOT LOCATION/0000 COUNTY Ness

660 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE NA SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 157.5' CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4,460' CEMENTED WITH Unknown SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4433-4438' (Perfs)

ELEVATION 2585' T.D. 4,460' PBDT 4,548' ANHYDRITE DEPTH 1,730'
(~~2585'~~ (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @4385' & dump 4 Sx. Cmt. on CIBP. Perf 5 1/2" Csg. @ 1100'. RIH w/Tbg. to 1750' (anhydrite) & pmp. 234 cu. ft. Cmt. TOH w/TBG. Pump 80 Sx Cmt. down 5 1/2" Csg. & observe 5 1/2" x 8-5/8" annulus. If no circulation, pump 150 Sx. Cmt. down 5 1/2" x 8-5/8" annulus.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Unknown

If not explain why? No ACO-1 in current files.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wes Willimon PHONE# (316) 626-8131

ADDRESS P. O. Box 2161 City/State Liberal, KS. 67905-2161

PLUGGING CONTRACTOR Cheyenne Well Service KCC LICENSE # 06454 ^{6/00}
(company name) (contractor's)

ADDRESS Box 384 Ness City, KS. 67560 PHONE # (785) 798-2282

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Aug. 1, 1999

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: July 26, 1999 AUTHORIZED OPERATOR/AGENT: Wes Willimon
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

July 29, 1999

Ensign Operating Company
P.O. Box 2161
Liberal, Ks. 67905-2161

Potter #1
API 15-135-00510-00-00
W/2 NW NW
Sec. 25-17S-25W
Ness County

Dear Wes Willimon:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888