

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME P. Potter

WELL NUMBER 2

 Ft. from S Section Line

 SW NE SW Ft. from E Section Line

SEC. 24 TWP. 17 SRGE. 25 (E) or (W)

COUNTY Hness

Date Well Completed 2/9/56

Plugging Commenced 6/20/2001

Plugging Completed 6/20/2001

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# 785 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/2001 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	252	9 5/8		
	Casing	0	4449	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Pump 41 bbl. water take rate 5 1/2 BPM 1100#. Dump 200# hulls with 40 sks. 60/40 pos, 6% gel with 100# hulls. Pump 46 bbl. jell space (15 sks). then 35 bbl. 60/40 poz, 6% gel. Displace 4 bbl. Shut off. Perf. at 550'. Mix 10 sk. 60/40 6%. Pressure to 3000#. Hook up to 9 5/8 and 5 1/2. PSI to 500#. Tie onto 5 1/2-4 1/2 and PSI to 500#. Release PSI and tore down.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601 **RECEIVED**
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss. **JUN 22 2001**

Mr. Mark Leiker (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
ROSEMARY SMITH
My Appl. Exp. 5/10/2003

(Signature) Mark Leiker

(Address) Box 723 Hays, Mo. 67601

SUBSCRIBED AND SWORN TO before me this 31 day of June, 2001

Rosemary Smith
Notary Public

My Commission Expires: 5/10/2003

OR