

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 18 TWP. 17 RGE. 25W E/W
Location as in quarters or footage from lines:
C SE SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well.
correctly on above
Section Platt.

Lease Owner Pickrell Drilling Company
Lease Name Norton K-E Well No. #2
Office Address 205 Litwin Bldg. 110 N. Market Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 9-8-81
Plugging completed 9-10-81
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 4497'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 218' | none |
| | | | | 5-1/2" | 4482' | 760' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in on location, got 7" stretch, knocked out bridge @700', ran sand to 4450' and set 5 sacks cement. Shot pipe @1031', and 765'. Pulled a total of 23 joints of pipe. Plugged well with 3 sacks hulls, 10 sacks gel, 8-5/8" plug, 180 sacks 50/50 pos, 6% gel. Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 81

My Commission expires:



James Hoover
Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Nat'l Bank Bldg.
Wichita, Ks, 67202

Rotary Drilling Commenced 11-18-74

Rotary Drilling Completed 12-19-74

LOCATION: Norton K-E #2
C SE SE 18-17-25W
Trego County, Kansas

15-135-20654-00-00

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 8 5/8 surface casing set at 218' and cemented with 150 sacks. Job completed 11-18-74.
5 1/2" set at 4482 with 160 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

| | |
|-------------------------|------|
| Clay & Post rock | 160 |
| Shale | 221 |
| Shale | 350 |
| Shale, Shells & Red Bed | 1358 |
| Sand | 1380 |
| Sand | 1590 |
| Shale | 1859 |
| Anhy | 1900 |
| Shale | 2370 |
| Shale & Lime Stringers | 2660 |
| Lime & Shale | 2795 |
| Shale | 2930 |
| Shale & Lime | 3110 |
| Lime & Shale | 3255 |
| Lime & Shale | 3380 |
| Lime & Shale | 3505 |
| Lime & Shale | 3570 |
| Shale & Lime | 3730 |
| Lime & Shale | 3885 |
| Lime | 3960 |
| Lime | 4065 |
| Lime & Shale | 4135 |
| Lime | 4215 |
| Lime | 4280 |
| Lime | 4315 |
| Lime | 4385 |
| Lime & Shale | 4406 |
| Lime | 4428 |
| Shale & Lime | 4479 |
| Miss Dolomite | 4490 |
| Mississippi | 4497 |

RECEIVED
STATE CORPORATION COMMISSION
JUN - 21 - 1975
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
Attorney-in-Fact

C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 30 day of January, 19 75, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires August 19, 1975

[Signature]
Notary Public
Helen L. Martin