


15-051-04312-00-00  
WELL PLUGGING RECORD

See All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 26, Twp. 13 Rge. 20 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines S/2 SE SE  
Lease Owner Leo J. Dreiling  
Lease Name Weisner Well No. 1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 9-23 19 61  
Application for plugging filed 6-8 19 63  
Application for plugging approved 6-10 19 63  
Plugging commenced 6-12 19 63  
Plugging completed 6-14 19 63  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 5-15 19 62  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3830 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	220	none
				5 1/2	3819	3013

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 3800'. Mixed and dumped 4 sx. cement.  
Pulled 5 1/2" casing to 550'. Mixed and circulated 13 sx. gel mud.  
Mixed and pumped in 20 sx. cement. Pulled casing to 200'. Mixed  
and pumped in 20 sx. cement. Pulled rest of casing. Filled hole  
with mud to 35'. Set 5' rock bridge. Mixed and put in 10 sx.  
cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ace Pipe Pulling Company License # 2  
Address Box 304 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Wm. D. Hoberecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Wm. D. Hoberecht

(Signature) \_\_\_\_\_  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

Notary Public.

My commission expires \_\_\_\_\_



L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company	Icer Addis Great Bend, Kansas	Sec.	26	Twp.	13	Rng.	20
Farm	Weisner	No.	1	Location	CS/1/2 SE SE		
Total Depth	3830'	County	Ellis County, Kansas				
Comm.	8-13-61	Comp.	8-23-61	Elevation:	D. F. 2186'		
Contractor	Triangle Drilling Co. Great Bend, Kansas						G. R.
	Casing Record	Cement Record	Production:				
	8 5/8" - - - - - 224'	170 sacks cement	Arbuckle				
	5 1/2" - - - - - 3819'	100 sacks cement					

15.051.0432.00.00

Figures Indicate Bottom of Formations

0 - 50	Post Rock
50 - 85	Post Rock & Surface Clay
85 - 105	Post Rock & Surface Clay
105 - 222	Shale
222 - 480	Shale
480 - 695	Shale & Sand
695 - 965	Shale & Sand
965 - 1190	Sand
1190 - 1487	Red Bed
1487 - 1534	Anhydrite
1534 - 1645	Shale & Shells
1645 - 2080	Shale & Shells
2080 - 2500	Lime & Shale
2500 - 2935	Lime & Shale
2935 - 3184	Lime & Shale
3184 - 3348	Lime
3348 - 3560	Lime
3560 - 3645	Lime
3645 - 3775	Lime
3775 - 3830	Lime
3830	TD

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 25 1963

CONSERVATION DIVISION  
VICTORIA, KANSAS

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the Leo J. Dreiling Oil, Company upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Weisner No. 1.

*Leo F. Dreiling*  
\_\_\_\_\_  
LEO F. DREILING

Subscribed and sworn to before me this 22 nd day of June, 1963.

*Roman Zimmerman*  
\_\_\_\_\_  
NOTARY PUBLIC

My Commission Expires: August 14, 1965

