

15135-21238-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 35 Twp. 17S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines _____
Martin Oil Company

Lease Owner _____

Lease Name _____ Well No. 1

Office Address _____ 527 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) _____ Dry Hole

Date well completed _____ August 18 19 76

Application for plugging filed _____ August 18 19 76

Application for plugging approved _____ August 18 19 76

Plugging commenced _____ August 18 19 76

Plugging completed _____ August 18 19 76

Reason for abandonment of well or producing formation _____ Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____ Yes

Name of Conservation Agent who supervised plugging of this well _____ Leo Massey, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4380 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	286'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 720' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 7:40 A. M. August 18, 1976.

RECEIVED
STATE CORPORATION COMMISSION

SEP 02 1976

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____ Strata Drilling Company

Address _____ P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Kenneth J. Link (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____ Kenneth J. Link, President

_____ P. O. Box 355, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 23rd day of August, 1976

_____ Elaine H. Taylor, Notary Public

My commission expires _____ December 14, 1977



15-135-21238-0000

DRILLERS LOG

#1 Krug

CASING RECORD:
281.30' of new 8-5/8"
surface casing.

COMPANY: Martin Oil Company
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/NW SW
Section 35-17S-25W
Ness County, Kansas

TOTAL DEPTH:
4380'

COMMENCED: August 9, 1976
COMPLETED: August 18, 1976

ELEVATION: 2408' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil, Post Rock and Shale	0	300	Ran 281.30' of new 8-5/8" surface casing; set and cemented at 286' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 2:15 A. M. August 10, 1976.
Shale	300	850	
Shale, Sand & Shale	850	1525	
Shale	1525	2378	
Lime & Shale	2378	4105	
Lime	4105	4210	
Lime & Shale	4210	4270	
Lime	4270	4335	
Lime & Shale	4335	4380	

ROTARY TOTAL DEPTH: 4380'

No electric log was run.

D. & A.

RECEIVED
STATE CORPORATION COMMISSION
SEP 02 1976
CONSERVATION DIVISION
Wichita, Kansas

Plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 7:40 A. M. August 18, 1976.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 23rd day of August, 1976.

My Commission Expires:



Elaine H. Taylor
Elaine H. Taylor, Notary Public