

15-135-20235-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
04-23-1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Co., Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name Irvin Well No. 1

Location G SW SE Sec. 32 Twp. 16 Rge. 21 (E) (W) XX

County Ness Total Depth 4289

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 7P Day 21 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4289' 8 5/8 csg set at 568' cwc Gmt mat. 50-50 poz cmt W/6% total gel.

Gurned pits, circulated heavy mud, set cementing plug at 660' and displaced 50 sk cmt thru drill pipe. Heavy mud to 550' set cementing plug and displaced 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug 3 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Measey  
Well Plugging Supervisor

INVOICED

DATE 4/23/69  
INV. NO. 9648-u