

15-135-20176-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
09-14-1970

Operator's Full Name Petroleum, Inc.

Complete Address Route 2 Great Bend, Kansas 67530

Lease Name North "D" Well No. 1

Location C SE SE Sec. 29 Twp. 16 Rge. (E) (W) 21

County Ness Total Depth 4280

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn & Smith

Address Ellinwood, Kansas License No. 396

Operation Completed: Hour 10 A Day 12 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 4280' 8 5/8 csg set at 289' cwc

5 1/2 csg set at 4278' cw 100 sk cmt.

5 1/2 csg PBSD 4203' with top perf. (4180-4135) Sand back 5 1/2 csg to 4100'

Cutoff and recovered 2233' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls - 100 sk 6% poz - 5 sk gel - plug and 20 sk 6% poz. Max. pres. 600 lbs.

Gmt. (0-90) gel (90-250) Gmt. (250-550) gel (550-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mansley  
Well Plugging Supervisor

DATE 9-14-70

INV. NO. 2520-W