

15-135-20949-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 3 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-03-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John W. Scherzinger  
Complete Address 7721 State Line Rd, Suite 105, Kansas City, Missouri 64114  
Lease Name Scherzinger Well No. 1  
Location NW NW NE Sec. 23 Twp. 16 Rge. (E) (W) 24  
County Ness Total Depth 4536'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor DNB Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 2:30 A Day 2 Month 12 Year 1974

The above well was plugged as follows:

BTD 4536' 8 5/8 csg set at 284' cwc 200 sx. Plg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, displaced 70 sk cmt plug at 800' thru drill pipe.  
Heavy mud to 240' & set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set  
cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Z. Massey  
Well Plugging Supervisor

DATE 12/4/74

INV. NO. 411-W