

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,596-00-00 (of this well)

Operator's Full Name Pendleton Land & Development, Inc.

Complete Address 1410 Security Life Bldg., Denver, Co.

Lease Name Anderson Well No. 1

Location C SE SW Sec 22 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4622'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 1:30 P Day 18 Month 3 Year 1979

The above well was plugged as follows:

RTD 4622' 8 5/8 csg set 280' cwc 185 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1979
03-20-1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-20-79
INV. NO. 9294-W