

15-135-20751-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
MAY 23 1973
CONSERVATION DIVISION
Wichita, Kansas
05-23-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling Company

Complete Address 801 Union Center Wichita, Kansas

Lease Name Nuttle Well No. 1

Location NW NW Sec. 19 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4530'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12 P Day 21 Month 5 Year 1973

The above well was plugged as follows:

RTD 4530' '8 5/8 csg set at 266' cwc: Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 5/23/73

INV. NO. 9402-W