

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135 -21,361-00-00 (for this well)

RECEIVED
STATE CORPORATION COMMISSION
09-23-1977
SEP 23 1977
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beren Corporation
Complete Address 970 Fourth Financial Center, Wichita, Kansas
Lease Name Strickler Well No. 1
Location C SW SE Sec. 10 Twp. 16 Rge. (E) (W) 24
County Ness Total Depth 4560'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 6:45 A Day 22 Month 9 Year 1977

The above well was plugged as follows:

RTD 4560' 8 5/8 csg set 338' cwc 200 sk. Plg. Mat. 50-50 poz 64 total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo M. Massey
Well Plugging Supervisor

DATE

9-23-77

INV. NO.

5889-4