

15-135-20583-00-00

Form CP-3
Rev. 6-4-68

KANSAS

[Handwritten mark]

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1972

CONSERVATION DIVISION
Wichita, Kansas

D4-10-1972

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Flax Well No. 1

Location NW NW SW Sec. 8 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4489'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson (Rotary)

Address License No.

Operation Completed: Hour 3:45 A Day 8 Month 4 Year 1972

The above well was plugged as follows:

RTD 4489' 8 5/8 csg set at 326' cwc Cmt. Mat. 50-50 poz W/6% total Gelth
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 24-11-72

INV. NO. 5502-W