

15-135-20541-00-00

67

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas

01-18-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Geiss "B" Well No. 1

Location SW SE NW Sec. 7 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4535'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Rains & Williamson (Rotary)

Address Wichita, Kansas License No.     

Operation Completed: Hour 5:15 P Day 16 Month 1 Year 1972

The above well was plugged as follows:

RTD 4535' @ 5/8 csg set at 326' CWC Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1-18-72  
INV. NO. 5031-W