

15-135-20589-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1972
CONSERVATION DIVISION
Wichita, Kansas
03-20-1972

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18007 Wichita, Kansas

Lease Name Kahler Well No. 1

Location SW SE NE NENENE Sec. 6 Twp. 16 Rge. 1 (E) (W) 24

County Ness Total Depth 4525'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson (Rotary)

Address Wichita, Kansas License No.

Operation Completed: Hour 2 A Day 16 Month 3 Year 1972

The above well was plugged as follows:

RTD 4525' 8 5/8 csg set at 330' cwc 200 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 3-24-72

INV. NO. 5398-W