

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

[Handwritten mark]

API Number 15- 135-22096-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Post Rock Oil Inc.

Complete Address Box 5 La Cross Ks. 67548

Lease Name Flax Well No. #1

Location 215 WEC - 1200' NSL Sec. 1 Twp. 16 Rge. 24 (East) (West)

County Neosho Total Depth 4555'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Blue Goose Dr. Co.

Address Box 1413 G.B. Ks. License No. _____

Operation Completed: Hour: 9:00 ^{AM} Day: 4 Month: 9 Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

- 8 5/8" - 337' S.A. - 225 SK Common Cm. 2% Gel. - 3% CA-CC
- Ordered 120 SK 50/50 Pozmix 4% Gel. - 3% CA-CC. + 8 5/8" plug
- SP. Drill Stem - with heavy mud Between all plugs
- 1st plug 900' - w/ 60 SK cm.
- 2nd 350' w/ 40 SK cm.
- 3rd Solid Bridge Hubs - plug @ 40'-0' 10 SK cm
- 5th 5 SK Rat hole
- 6th 5 SK Mouse hole Cm. By Haliburton

RECEIVED
STATE CORPORATION COMMISSION
09-08-1981
SEP - 8 1981

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10-30-81

INV. NO. 8192-W

Signed: [Signature]
Conservation Division Agent