


15-135-20119-00-00

Form CP-3  
Rev. 6-26-62

  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name M & O Oil Co., Inc. 02-26-1968

Complete Address: Box 791 Fort Scott, Kansas 66701

Lease Name Sunley Well No. 1

Location C SE NW Sec. 13 Twp. 16 Rge. 22 (E) (W) X

County Ness Total Depth 4391

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Hellar Drlg.

Address: Wichita, Ks. License No.     


Operation Completed: Hour 10 P Day 23 Month 2 Year 1968

The Above well was plugged as follows:

RTD 4391' 8 5/8 csg set at 230' cwc 175 sc. Cem Mat. 50-50 poz cement W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 2/26/68  
INV. NO. 7309-W