

15-135-20840-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1974
03-13-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Oil Company
Complete Address 200 W. Douglas, Wichita, Kansas
Lease Name Hogsett Well No. 1
Location SW NE NW Sec. 8 Twp. 16 Rge. (E) (W) 22
County Ness Total Depth 4630'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 2 P Day 11 Month 3 Year 1974

The above well was plugged as follows:

RTD 4630' 8 5/8 csg set at 250' cwc 200 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 3/18/74
INV. NO. 8758-W