

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-135-20183-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1968
CONSERVATION DIVISION
Wichita, Kansas
09-12-1968

Operator's Full Name John C. Graves Et al

Complete Address: 505 Union Center Wichita, Kansas

Lease Name Wyman Well No. 1

Location App. C SE NW Sec. 4 Twp. 16 Rge. 22 (E) (W) XX

County Ness Total Depth 4425

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 2:15 A Day 11 Month 9 Year 1968

The Above well was plugged as follows:

RTD 4425' 8 5/8 csg set at 228' cwc: 150 sc. Cem. Mat. 100 sc 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INVOICED

DATE 9/12/68
INV. NO. 8449-11