

15-135-20889-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson
Complete Address 408 One-Twenty Bldg., Wichita, Kansas 67202
Lease Name Barrows "B" Well No. 1
Location C NW SE Sec. 31 Twp. 17 Rge. (E) (W) 25
County Ness Total Depth 4470'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Jims Pipe Pulling
Address Chase, Kansas 67524 License No. 739
Operation Completed: Hour 2:30 P Day 29 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 4470' 8 5/8 csg set 285' cwc 200 sx.
4 1/2 csg set 4469' cw 150 sx cem.
4 1/2 csg perf. (4361-4366)
Filled 4 1/2 csg W/snd (4469-4350) dumped 4 sx cem W/dump bailer. (4350-4315)
Cutoff & recovered A/2675') of 4 1/2 csg.
Pumped down 8 5/8 csg with 15 sx gel & water -60 sx 50-50 poz 6% -15 sx gel &
water -released 8 5/8 plug & pumped 60 sx 50-50 poz 6% by Hallib. PP 350-400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. E. Waddy
Well Plugging Supervisor

DATE 7/30/75
INV. NO. 1690-W