

KANSAS

Form **CP-3** RECEIVED
REV. 06-27-68 CONSERVATION COMMISSION

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

MAR 08 1976
03-08-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 135-21026-0000 of this well)

Operator's Full Name Twinn Western Resources, Inc.

Complete Address Suite 518 -- 200 E. 1st. -- Wichita, Kansas

Lease Name Marhofer Well No. 1

Location NE ~~SE~~ SW Sec. 30 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4554'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 3:15 A Day 5 Month 3 Year 1976

The above well was plugged as follows:

RTD 4554' 8 5/8 csg set 285' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-08-76

INV. NO. 2856-W