

15-135-20157-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bldg., Wichita, Kansas

Lease Name Dubbs "E" Well No. 2

Location C SE SW Sec. 26 Twp. 16 Rge. 24 (E) (W) X

County Ness Total Depth 4530'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12:30P Day 28 Month 6 Year 1968

The Above well was plugged as follows:

RTD 4530' 8 5/8 at 275' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud. set cementing plug at 900' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1968

CONSERVATION DIVISION
Wichita, Kansas

Signed: Geo. F. Murray
Well Plugging Supervisor

INVOICED

DATE 7-2-68

INV. NO. 8035-W

07-01-1968