

15-135-00322-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1968
CONSERVATION DIVISION
Wichita, Kansas
12-04-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Quality Supply Company

Complete Address: 6320 Jacqueline Wichita, Kansas 67208

Lease Name Dubbs Well No. E - 1

Location SW Sec. 26 Twp. 16 Rge. 24 (E) X (W) X

County Ness Total Depth 4615

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flowers Well Servicing Inc.

Address: E 9th Peabody, Kansas License No. 628

Operation Completed: Hour 6P Day 2 Month 12 Year 1968

The Above well was plugged as follows:

Total Depth 4615' 8 5/8 csg set at 270' cwc

5 1/2 csg set at 4615' cw 150 sc cmt.

5 1/2 csg perf. (4470-86)

Set 5 1/2 plug at 4400' Poured 10' sand and dumped 5 sc cmt. with dump bailed

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 25 sc gel W/4 sc hulls, 140 sc 50-50 poz cmt

with 6% total gel, 5 sc gel, 1 sc hulls 3 plug and 10 sc cement.

Gmt. (0-40) gel (40-240) Gmt (240-800) Gel (800-TD) Max. Pres. 500 lbs. SI pres 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio F. Messing
Well Plugging Supervisor

DATE 12/4/68

INV. NO. 8946-11