

1 030424

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,799 -00 700  
SE SW SW , SEC. 26 , T 16 S, R 22 W/X

330 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name F. Ummel Well # 2

Operator: A. Scott Ritchie  
Name &  
Address 125 North Market, Suite 950  
Wichita, KS 67202

County Ness  
Well Total Depth 4437 feet  
(Mississippi)

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 26 Month: May Year: 19 85

Plugging proposal received from Lloyd Dellett

(company name) Murfin (phone) 316-267-3241

Elevation 2384

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1713-50

1st plug at 1740' with 50 sx cement

2nd plug at 840' with 65 sx cement

3rd plug at 300' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:30 am Day: 26 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement, 2nd plug 840' with 65 sx

cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED

STATE CORPORATION COMMISSION

MAY 31 1985

05-31-1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed, observe this plugging.)

DATE 6-6-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 8353

5-26