

1 060061

10-1

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-22,632-00-00

NW SE SW, SEC. 26, T 16 S, R 22 W/X

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name F. Ummel Well # 1

Operator: Ritchie Exploration, Inc.

County Ness 144.32

Name & Address P.O. Box 783188

Well Total Depth 4441 feet

Wichita, KS 67278-3188

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 12:15 p.m. Day: 1 Month: 10 Year: 19 97

Plugging proposal received from Bennie Dills

(company name) Ritchie Exploration, Inc. (phone) 316-793-8969

were: 5 1/2" at 4435' w/100 sx cement, Perfs at 4313-16, 4316-21'

Pump 500 lbs. hulls, 35 sx cement 22 sx gel and 150 sx cement.

Check backside.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls, 35 sx cement, 22 sx gel, and 150 sx cement. Pressured to 1250 psi. Shut in with 500 psi.

Went down backside and pressured up to 500 psi immediately.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE

Signed Michael Maier (TECHNICIAN)

INV. NO. 49292

RECEIVED
STATE CORPORATION COMMISSION
OCT-9 12:04