

1 052087

API NUMBER 15- 135-23,546 -00-02 Kce

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SW, SEC. 26, T 16 S, R 22 W/8
400 feet from S section line
3040 feet from E section line

11-27

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name F. Ummel Well # 4
County Ness 144.62
Well Total Depth 4450 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address

Company to plug at: Hour: 9 a.m. Day: 27 Month: 11 Year: 1996

Plugging proposal received from John Neuberger

(company name) Ritchie Exploration, Inc. (phone) 316-793-8969

were: 5 1/2" at 4443' w/100 sx cement. PBD 4423', Perfs at 4301-28', Do Port collar at 1699' w/ 325 sx cement

1st plug pump 2 sx hulls and fill with cement.

Check backside.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:45 a.m. Day: 27 Month: 11 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 200 lbs. hulls and 350 sx cement. Maximum pressure 1000 psi and shut in 800 psi.

Visually checked the 8 5/8" X 5 1/2" annulus. It was full of cement.

12-05-1996

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 11 11:14

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 09 1996

INV. NO. 47147

Signed Richard W. Lacy (TECHNICIAN)