

1 120840

10-5

API NUMBER 15-135-23,435-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW, SEC. 33, T. 16 S, R. 22 W/X

990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Weeks Well # 1-33

Operator: Chief Drilling, Inc.

County Ness

Name & Address 120 S. Market, Ste. 300

Well Total Depth 4515 - 146.73 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 5 Month: 10 Year: 19 93

Plugging proposal received from Douglas Thimesch

(company name) Chief Drilling (phone) 316-262-3791

were: 4 1/2" at 4515' w/150 sx cement, PBSD 4460', Perfs at 4470-80, 4369-71', 1715' w/400 sx cement

1st plug pump 40 sx cement with 2 sx hulls on bottom, gel to 1800', cement to top,

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15 p.m. Day: 5 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 200 lbs. hulls, 40 sx cement, 13 sx gel, and 80 sx cement. Pumping pressure 0-700 psi and shut in 100 psi.

Pumped 1/2 bbl. water in 8 5/8" X 4 1/2" annulus-shut in pressure 800 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

If additional description is necessary, use BACK of this form.

DATE (did / XXXXXX) observe this plugging.

INVOICED
10-20-93
38990

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
10-14-1993
CONSERVATION DIVISION
Wichita, Kansas