

To: 1 090314 8-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,742-00-00
SE NW NE, SEC. 33, T. 16 S, R. 22 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling, Inc.
Name & Address 120 S. Market, Ste. 300
Wichita, KS 67202

4290 feet from S section line
1650 feet from E section line

Lease Name Hinnergardt Well # 1-33

County Ness 144.69

Well Total Depth 4452 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 120 S. Market, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 17 Month: 8 Year: 1993

Plugging proposal received from Gary Lindenmuth

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: 5 1/2" at 4448' w/125' sx cement, Perfs at 4426-36, 4412-14, 4418-21'

1st plug sand back to 4360' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1575' with 50 sx cement, 3rd plug at 1200' with 50 sx cement,

4th plug at 700' with 50 sx cement, 5th plug at 275' with 50 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 17 Month: 8 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3375' and dump 5 sx cement on top of sand through bailer, Plug through casing:

2nd plug at 1776' with 50 sx cement,

3rd plug at 1050' with 80 sx cement,

4th plug at 282' with 50 sx cement,

5th plug at 40' with 10 sx cement. Circulated cement to pit.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 8-24-93

WV. NO. 38404

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
08-19 1993
AUG 19 1993
CONSERVATION DIVISION
Wichita, Kansas