

1 070334

MAY 1 0 1987

135-23,111-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NE, SEC. 33, T 16 S, R 22 W/E

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Allen Miller Well # 1

Operator: Ritchie Exploration, Inc.

County Ness 145.34

Name & Address 125 North Market, Suite 1000

Well Total Depth 4472 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 231

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11:30 p.m. Day: 9 Month: 5 Year: 19 87

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 303-775-9454

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2412'

1st plug at base Anhydrite with 50 sx cement, 2nd plug at 1110' with 80 sx cement,

3rd plug at 240' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2 a.m. Day: 10 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1760' with 50 sx cement,

2nd plug at 1110' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED

Remarks: Used 60/40 Pozmix 6% gel by Allied.

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

INVOICED

60342 / did not observe this plugging.

MAY 12 1987 05-12-1987

DATE 5-15-87

Signed Dan (TECHNICIAN)

INV. NO. 16925

5-10

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date 4/16/87

API Number 15-135-23,111-00-00

OPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Rocky Milford
Phone 316/267-4375

NW SW NE Sec. 33, Twp. 16. S, Rg. 22. X West
36.30 Ft. from South Line of Section
23.10 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Ness

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, KS

Lease Name Allen Miller Well # 1
Ground surface elevation 2412 feet MSL

Well Drilled For: X Oil, Gas, OWWO
Well Class: Inj, Wildcat
Type Equipment: X Mud Rotary, Air Rotary, Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 50
Depth to bottom of usable water 10.20

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 - X
Surface pipe planned to be set 200

Operator
Well Name
Comp Date Old Total Depth

Conductor pipe required
Projected Total Depth 4450 feet

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.
Date 4/07/87 Signature of Operator or Agent Rocky Milford Title Geologist

Formation Cherokee

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.
This Authorization Expires 10-9-87 Approved By 4-9-87

SPUD 5-1-87
85/2 - 230.1

Previously assigned API 135-23,111-00-00

NW SW NE Sec. 33 Twp. 16. S, Rg. 22. X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 1700 or formation with 50 feet of cement
2nd plug @ ft. deep 850 or formation with 50 feet of
3rd plug @ ft. deep 330 or formation with 40 feet of
4th plug @ ft. deep 40 or formation with 10 feet of
5th plug @ ft. deep or formation with feet of

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Rodney Javel
TD 4472 FORMATION 2160
SURFACE PIPE 8 1/2" @ 231
ANEHYDRITE 1724-1760 ELEVATION 2412
STARTING TIME & DATE 1765 11:20 PM 5-9-87
COMPLETION TIME & DATE 2 AM 5-10-87
1st PLUG @ 1760 FT. WI 50 SX 80
2nd PLUG @ 160 FT. WI 80 SX 40
3rd PLUG @ 240 FT. WI 40 SX 10
4th PLUG @ 40-0 FT. WI 10 SX 15
RAT HOLE CIRCULATED WI 15-15 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI 15-15 SX
CEMENT COMPANY
TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION

MAY 12 1987
05-12-1987
CONSERVATION DIVISION
Wichita, Kansas