

308
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,527-00-00
SE SE NW, SEC. 32, T 16 S, R 22 WXR

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

2970 feet from S section line

2970 feet from E section line

Lease Name Wolfe "A" Well # 1

County Ness 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address 401 E. Douglas, #500, Wichita, KS 67202

Company to plug at: Hour: 12:01 a.m. Day: 19 Month: 12 Year: 19 90

Plugging proposal received from Bob Casper

(company name) White & Ellis Drilling Company (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1745-82'
1st plug at 1770' with 50 sx cement, 2nd plug at 810' with 80 sx cement,
3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 a.m. Day: 19 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1770' with 50 sx cement,
2nd plug at 810' with 80 sx cement,
3rd plug at 300' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1990
12-21-1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy) did not observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 2-7-91

INV. NO. 30581

EFFECTIVE DATE: 11-18-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL 15-135-23,527-00-00

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.L.C. five (5) days prior to commencing well

Expected Spud Date 11/19/90
month day year

SE SE NW Sec 32 Twp 16 S, Rg 22 East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Leah Ann Kasten
Phone: 316/267-4375

2970 feet from South line of Section
2970 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling Co.

County: Ness
Lease Name: Wolfe, "A" Well #: 1
Field Name: wildcat
Is this a Prorated Field? yes X no
Target Formation(s): Cherokee
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2418' est. GL. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 260'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: none
Projected Total Depth: 4480'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations: well farm pond X other
DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:
250' Alt. II Req.

Well Drilled For: Well Class: Type Equipment:
X. Oil ... Inj ... Infield X. Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... DWFO ... Disposal X. Wildcat ... Cable
... Seismic; ... # of Holes

If DWFO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Exp. 5/13/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following information is true and correct:

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

DEC 21 1990
12211990
Wichita, Kansas

Pusher Bob Capps Don Ormel -
SPUD DATE 12-9-90 INIT. CM
LENGTH SURFACE PLANNED 263
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when doné bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 263 CONDUCTOR
ANHYDRITE T-1745 B-1782 ELEVATION
4500
TD 4480 FORMATION Miss
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 1990 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 810 Ft. W/ 80 SX Flow Seal
3 Bottom Surface @ 300 Ft. W/ 50 SX
4 40' Plug @ 40- Ft. W/ 10 SX plug
RAT HOLE CIRC/W/5 SX MOUSE HOLE W/10 SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN SD DATE 12/14/90
TYPE OF CEMENT 60/40 6 1/6 gal.
STARTING TIME 12:01 (AM/PM) DATE 12-19-90
COMPLETION TIME 3:30 (AM/PM) DATE 12-19-90
CEMENT COMPANY ACCIED

Drum 2 EW 1 1/2 S 1/2 E 156