

1 070994

10-24

API NUMBER 15-135-23,615-00-00 279

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SW SW, SEC. 32, T. 16 S, R. 22 W15R

330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Musselman Well # 2

Operator: Ritchie Exploration, Inc.  
Name & Address 125 N. Market, Suite 1000  
Wichita, KS 67202

County Ness 178.42

Well Total Depth 5490 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12:05 p.m. Day: 24 Month: 10 Year: 19 91

Plugging proposal received from Lloyd Dellette

(company name) Murfin Drilling Company (phone) 316-267-3241  
Elevation 2391'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1716-44'

1st plug at 1770' with 50 sx cement, 2nd plug at 1100' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 250' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1750' with 50 sx cement,

2nd plug at 1100' with 80 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 250' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-30-1991  
OCT 30 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-14-91

33721

Signed Dan Gordon (TECHNICIAN)

FOR KCC USE:

EFFECTIVE DATE: 10-9-91

DISTRICT #

SSA? Yes X No

State of Kansas

NOTICE OF INTENTION TO DRILL

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10/09/91 month day year

Spot SW SW SW Sec 32 Twp 16 S. Rg 22 East West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: 125 N. Market, Suite 1000 City/State/Zip: Wichita, KS 67202 Contact Person: Bob Mathiesen Phone: 316/267-4375

330 feet from South-North line of Section 330 feet from East/West line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side) County: Ness

CONTRACTOR: License #: 30606 Name: Murfin Drilling Co.

Lease Name: Musselman Well #: 2 Field Name: Weeks North

Is this a Prorated/Spaced Field? yes X no Target Formation(s): Mississippian

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield X Mud Rotary Gas Storage X Pool Ext Air Rotary OWWO Disposal Wildcat Cable Seismic # of Holes Other

Nearest Lease or unit boundary: 330' Ground Surface Elevation: 2391 (est) feet MSL

Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no

If OWWO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Depth to bottom of fresh water: 100' Depth to bottom of usable water: 900' Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 200' Length of Conductor pipe required: none

Projected Total Depth: 4400' Formation at Total Depth: Mississippian

Water Source for Drilling Operations: well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

DWR Permit #: Will Cores Be Taken? yes X no If yes, proposed zone:

Exp. 4/4/92

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to spudding of well:

Pusher Lloyd Hellett SPUD DATE 10-13-91 INIT. DR. LENGTH SURFACE PLANNED

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLE AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8 @ 2' CONDUCTOR ANHYDRITE T- 1716 B- 1744 ELEVATION

TD 4490 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX

1 Anhydrite Base @ 1770 Ft. W/ 50 SX

2 1/2 Base Anyh. @ 1100 Ft. W/ 80 SX

3 1/2, 1/2 Plug @ 650 Ft. W/ 50 SX

4 Bottom Surface @ 250 Ft. W/ 50 SX

5 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN CM DATE 10-15-91

TYPE OF CEMENT 60/40 670 14 #5/sec

STARTING TIME 12:15 (AM/PM) DATE 10-24-91

COMPLETION TIME 3:30 (AM/PM) DATE 10-24-91

CEMENT COMPANY A.H. Al.