

To: 1 052140 6-12  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-24,004 -00-00  
SE SW NW, SEC. 32, T 16 S, R 22 W/X  
2310 feet from NXX section line  
990 feet from WXX section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name & Address: P.O. Box 783188  
Wichita, KS 67278

Lease Name Blanche Wolfe Well # 1  
County Ness 146.90  
Well Total Depth 4520 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co. Inc. License Number 5929  
Address 310 W. Central, Ste. 202, Wichita, KS 67202-1004

Company to plug at: Hour: 4:30 p.m. Day: 12 Month: 6 Year: 1997

Plugging proposal received from Rich Wheeler  
(company name) Duke Drilling Co. Inc. (phone) 316-267-1331

was: to fill hole with heavy mud and spot cement through drill pipe 1759-95'  
1st plug at 1790' with 50 sx cement, 2nd plug at 900' with 80 sx cement,  
3rd plug at 500' with 40 sx cement, 4th plug at 260' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6 p.m. Day: 12 Month: 6 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 1790' with 50 sx cement,  
2nd plug at 900' with 80 sx cement,  
3rd plug at 500' with 50 sx cement,  
4th plug at 260' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

06-17-1997

RECEIVED  
KANSAS CORP COM  
JUN 17 11:30

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXX) did not observe this plugging.

DATE 6-18-97

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 48376  
6-12

State of Kansas

135-24,004

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

EFFECTIVE DATE: 5-20-97

DISTRICT # 1  
SSA78 Yes No

Expected Spud Date 5 month 26 day 97 year

SE SW NW Sec 32 Twp 16 S. Rg 22W East West

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: P.O. Box 783188  
City/State/Zip: Wichita, KS 67278  
Contact Person: Lisa Thimmesch  
Phone: (316) 691-9500

2310 feet from South / North line of Section  
990 feet from East / West line of Section  
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Ness  
Lease Name: Blanche Wolfe well # 1  
Field Name: wildcat

CONTRACTOR: License # 5929  
Name: Duke Drilling

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Cherokee  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: 2430 est. feet MSL

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 200  
Depth to bottom of usable water: 900

If OLD: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth:

Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 280 MIN.  
Length of Conductor pipe required: none  
Projected Total Depth: 4500'

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:  
Exp. 11/15/97

Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond X other  
DWR Permit #:  
Will Cores Be Taken?: yes X no

AFFIDAVIT

220' Alt. Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements shall be observed:

Pusher Rich Wheeler

SPUD DATE 6-3-97 INIT. zn

LENGTH SURFACE PLANNED 220'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8 @ 2 1/2 CONDUCTOR  
ANHYDRITE T- 1759 B- 1795 ELEVATION

TD 4520 FORMATION

RAN PIPE @	DV TOOL	ALT II DONE
	SX	Y N
Arbuckle Plug @	Ft. W/	SX
Hug./Council @	Ft. W/	SX
Anhydrite Base @	<u>1790</u> Ft. W/	<u>50</u> SX
1/2 Base Anyh. @	<u>900</u> Ft. W/	<u>80</u> SX
1/2, 1/2 Plug @	<u>500</u> Ft. W/	<u>40</u> SX
Bottom Surface @	<u>260</u> Ft. W/	<u>40</u> SX
40' Plug @	<u>40</u> Ft. W/	<u>10</u> SX
RAT HOLE CIRC/W <u>15</u> SX	MOUSE HOLE W/	SX
WATER WELL	SX (Irr. Well	Pond
TECHNICIAN <u>R.L.</u>	DATE <u>6-12-97</u>	Hauling
TYPE OF CEMENT <u>60/40 per 6' log of 1/4 floored</u>	DATE <u>6-12</u>	
STARTING TIME <u>4:30 PM</u>	DATE <u>6-12</u>	
COMPLETION TIME <u>6:00 AM/PM</u>	DATE <u>6-12</u>	
CEMENT COMPANY <u>Alford Country</u>		

06-17-1997