

1 060802

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,000-00-00
200' SE
NW NW SE, SEC. 22, T 16 S, R 22 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Company
Name & Address P. O. Box 2758
Wichita, KS 67201

2178 feet from S section line
2178 feet from E section line

Lease Name Walker Well # 1
County Ness 144.63

Well Total Depth 4450 Mississippi feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 N. Oliver, Wichita, KS 67208

Company to plug at: Hour: 11:00 am Day: 8 Month: February Year: 19 86

Plugging proposal received from Jack Taylor

(company name) DNB (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Bottom 1775
Elevation N/A

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug at 330' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
CONSERVATION DIVISION
(TECHNICIAN) KANSAS

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45 pm Day: 8 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1775' with 50 sx cement, 2nd plug at 1090' with 50 sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% ccoby Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(State / did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 1-17-86

INV. NO. 12632
2-8

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1/27/86 month day year

API Number 15-135-2300-02 SE East 200' NW. NW SE Sec. 22. Twp. 16 S, Rg 22 XX West 21.78 Ft. from South Line of Section 21.78 Ft. from East Line of Section

OPERATOR: License # 5144 Name Mull Drilling Company Address P.O. Box 2758 City/State/Zip Wichita, KS 67201 Contact Person Dallas E. Donner Phone 264-6366

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 530 feet County Ness

CONTRACTOR: License # 5476 Name DNB Drilling Inc City/State 535 N. Oliver, Wichita 67208

Lease Name Walker Well # #1 Ground surface elevation feet MSL

Well Drilled For: Well Class: Type Equipment: XX Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl XX Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes no Depth to bottom of fresh water 100 Depth to bottom of usable water 850

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 8 5/8" @ 300' Conductor pipe required Projected Total Depth 4500 feet Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus even fully plugging hole to KCC specifications. Date 1/21/86 Signature of Operator or Agent Dallas E. Donner Title Geologist

For KCC Use: Conductor Pipe Required 7-27-86 feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 2-3-86 Approved By 1-21-86

move 2-3-86 8 5/8" @ 300' 200 2 200 feet per Alt. NO

200' SE, NW. NW SE Sec. 22. Twp. 16 S, Rg. 22 XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (e.g., 2040', 1230', 330', 40', 15'), feet depth with, sxs of, and material (e.g., 60-40. poz., .2% gel, .3% cc).

Vertical list of well parameters: PUSHER Jacob Taylor, TD 4450 FORMATION MISS, SURFACE PIPE 8 7/8 @ 329, ANHYDRITE 1775 ELEVATION 1500m, STARTING TIME & DATE, COMPLETION TIME & DATE 12:45 PM 2-8-86, 1st PLUG @ 1775 FT. W/ 50 SX, 2nd PLUG @ 1090 FT. W/ 50 SX, 3rd PLUG @ 400 FT. W/ 50 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ Hard - SX, CEMENT COMPANY Applied, TECHNICIAN any

RECEIVED STATE CORPORATION COMMISSION FEB 17 1986 CONSERVATION DIVISION Wichita, Kansas 02-17-1984