

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135 22, 312-00-08

NE NW NW Sec. 20, T 16 S, R 22 W

330 feet from N/B section line

990 feet from W/B section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name Downey Well # 1

Operator: Sunburst Exploration Inc.
Name & Address 708, one Main Place
Wichita Kans. 67202

County Ness

Well Total Depth 4510 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 279'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Inc. License Number 5104

Address Box 1413, Great Bend, Kans 67530

Company to plug at: Hour: 8:00 AM, Day: 19 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Leroy Bowen

(company name) Blue Goose Drilling Co Inc (phone) _____

were: 1st plug @ 1680' w/ 60 sbp cement. 2nd plug @ 330' w/ 40 sbp cement. 3rd plug @ 40' to 0' on solid bridge w/ 10 sbp cement. Circulate 10 sbp cement in rat hole. Use 50/50 pro cement w/ 2% gel & 3% C.C. The plugging was accomplished by Halliburton Co.

Signed Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 AM, Day: 19 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT This hole was plugged as orders given in above paragraph.

Remarks: _____

STATE CORPORATION COMMISSION
RECEIVED
12-22-1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

INVOICED
DATE 1-30-83
INV. NO. 2244-W