

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1 031338 <sup>Rec'd</sup> 04-25-1990-30

API NUMBER 15-135-23,462-00-00 <sup>14 P</sup>  
110' N of C SW SE, SEC. 19, T 16 S, R 22 W/EX  
770 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_

Operator: Kansas Corporation Commission  
Name & Address 130 S. Market, Rm. 2078  
Wichita, KS 67202

Lease Name Wierman Well # 1

County Ness

Well Total Depth 4450 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 28 Month: 6 Year: 1995

Plugging proposal received from Steve Durrant

(company name) KCC (phone) 316-225-6760

were: 5 1/2" at 4441', PBD 4440', Perfs at 4434-?'

Run line to find bridge, knock out bridge, push wooden plug to 4016', dump sand and 4 sx cement

Mix and pump 130 sx cement down 4 1/2" casing.

Pump 200 sx cement down annulus.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:15 p.m. Day: 30 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 6/28/95 Found bridge at 1200'. Spudded through. Pushed wooden plug to 4016', dumped sand and 4 sx cement.

6/30/95 Shot hole in casing at 1000'. Est. injection rate. Mixed and pumped 130 sx cement down 4 1/2" casing (slight blow on annulus).

Pumped 200 sx cement down annulus. Shut in pressure 200 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Steve Durrant  
(TECHNICIAN)