

6-5

To: 1 070956  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,563-00-00

SW NE SE, SEC. 12, T. 16 S, R. 22 W/E

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Richardson "D" Well # 1

Operator: Bankoff Oil Company

County Ness 142.28

Name & Address P.O. Box 1374

Well Total Depth 4378 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 5 Month: 6 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4377' w/100 sx cement, Perfs at 4282-85'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 80 sx cement at 1600',

3rd plug pump 50 sx cement at 1000',

4th plug pump 40 sx cement at 300', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 5 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4230' and dumped 5 sx cement on top

of sand through bailer,

2nd plug pulled casing to 1580' and pumped 50 sx cement,

3rd plug pulled to 1000' and pumped 80 sx cement,

4th plug pulled to 300' and pumped 40 sx cement,

5th plug pulled all casing and topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
06-10-1991  
JUN 10 1991  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

(if applicable) observe this plugging.

DATE 6-14-91

Signed Dan Goodrow  
(TECHNICIAN)

INV. NO. 32131