

1 070812

A NB 5-28
ECC

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,463-00-00
80' W & 110' S
NE SE NW, SEC. 8, T 16 S, R 22 W/E
3520 feet from Section line
3710 feet from Section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30336

Lease Name Wierman Well

Operator: Sunflower Exploration
Name &

County Ness

Address Rt. 1, Box 5

Well Total Depth 4390 feet

Brownell, KS 67521

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 11 a.m. Day: 28 Month: 5 Year: 19 90

Plugging proposal received from Jack Fox

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1725-61'

1st plug at 1780' with 50 sx cement, 2nd plug at 900' with 80 sx cement,

3rd plug at 250' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45 p.m. Day: 28 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1780' with 50 sx cement,

2nd plug at 900' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if did not observe this plugging.)

DATE 6-6-90

Signed Dan Goodrow
(TECHNICIAN)

WELL NO. 28344

FORM MUST BE TYPED
FORM C-1 12/88

EFFECTIVE DATE: _____

State of Kansas

15-135-23,463-00-00

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date MAY 5 1990
month day year

80' W & 110' S
NE. SE. NW. Sec 8. Twp 30 S R. 10 E

OPERATOR: License # 30336
Name: SUNFLOWER EXPLORATION
Address: RT. 1 BOX 5
City/State/Zip: BROWNELL, KANSAS 67521
Contact Person: RON NELSON
Phone: 913-628-3449

3520' feet from South line of Section
3710' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 8241
Name: EMPHASIS OIL OPERATIONS

County: NESS
Lease Name: WIERMAN Well #: 1
Field Name: WILDCAT

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWO Disposal X Wildcat Cable
Seismic: # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): LKC, QHER, SAND, MISS
Nearest lease or unit boundary: 440'
Ground Surface Elevation: 2376' feet MSL

If OWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 100' est.
Depth to bottom of usable water: 800' est. 813
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: NONE
Projected Total Depth: 4350'
Formation at Total Depth: MISSISSIPPI
Water Source for Drilling Operations:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: XXXXXXXXXXXXXXXXXXXXX

DWR Permit #: well X farm pond other
Will Cores Be Taken? yes X no
If yes, proposed zone: XXXXXXXXXXXXXXXXXXXXX

Exp. 11/1/90

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well shall be in accordance with K.S.A. 55-101, et. seq. It is agreed that the following items:

Pusher	Jack Fox	TD	4370	FORMATION	MISS	CONDUCTOR	
SURFACE PIPE	8 7/8" @ 225'	ANHYDRITE T-	1725'	B-	1761'	ELEVATION	
STARTING TIME	11:00 (AM/PM)	DATE	5-28-90	COMPLETION TIME	12:45 (AM/PM)	DATE	11
PLUG NO.		Arbuckle Plug @		Ft.	W/	SX	
		Hug./Council @		Ft.	W/	SX	
1		Anhydrite Base @	1780	Ft.	W/	50	SX
2		1/2 Base Anyh. @	900	Ft.	W/	80	SX
		1/2, 1/2 Plug @		Ft.	W/	SX	
3		Bottom Surface @	250	Ft.	W/	40	SX
4		40' Plug @	40	Ft.	W/	10	SX
RAT HOLE CIRCULATED W/			15			SX	
MOUSE HOLE CIRCULATED W/						SX	
WATER WELL PLUGGED W/						SX	
CEMENT COMPANY	DG	DATE	5-25-90	TECHNICIAN	DG		
TYPE OF CEMENT	60/40 6% 1/4 # FS						
SPUD DATE	5-21-90	INIT.	MS				
LENGTH SURFACE PLANNED	200'						
RESERVE PIT STATUS-	REMOVE FLUID						LINED

TRACT DRILLING ALONE ONLY