

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24212-00-00
Spot: NWNWSEW Sec/Twnshp/Rge: 6-16S-22W
1475 feet from N Section Line, 1480 feet from W Section Line
Lease/Unit Name: LOUISE Well Number: 1-6
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

Surface Casing Size: 8.625 feet: 224

\$ 144 63

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2003 10:40 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (316) 262-1378

Proposed Plugging Method: 1ST PLUG AT 1740'W TIH 50 SX CMT. 2ND PLUG AT 1120' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 30 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/24/2003 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1740' WITH 50 SX CMT. CIRCULATED HOLE WITH MUD FROM DRILLING RIG FIRST. 2ND PLUG AT 1120' WITH 80 SX CMT. CIRCULATED HOLE WITH MUD FROM DRILLING RIG FIRST. 3RD PLUG AT 600' WITH 30 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
AUG 04 2003
KCC WICHITA
08-04-2003

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
JUL 30 2003
KCC Dodge City

Signed Michael J. Maier
(TECHNICIAN)

INVOICED

DATE 8-5-03

INV. NO. 2004060328

[Handwritten signature]