

1 040572

10-8  
API NUMBER 19-135-23,599-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N/2 NW SE, SEC. 3, T. 16 S, R. 22 W/EX

2310 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Lease Name Dinkel Well # 1

Operator: Charter Production Company  
Name & Address: 224 E. Douglas, Suite 400  
Wichita, KS 67202

County Ness 145.27

Well Total Depth 4470 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 7:15 a.m. Day: 8 Month: 10 Year: 19 91

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1776-1816'

1st plug at 1816' with 50 sx cement, 2nd plug at 950' with 80 sx cement,

3rd plug at 500' with 50 sx cement, 4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 a.m. Day: 8 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1820' with 50 sx cement,

2nd plug at 950' with 80 sx cement,

3rd plug at 500' with 50 sx cement,

4th plug at 260' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If not observed, observe this plugging.)

Signed *Steve Pfeifer* (TECHNICIAN)

DATE 10-29-91

INV. NO. 33543

RECEIVED  
STATE CORPORATION COMMISSION  
10-15-1991  
OCT 15 1991  
CONSERVATION DIVISION  
Wichita, Kansas

FOR KCC USE:

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 9-4-91

State of Kansas

NOTICE OF INTENTION TO DRILL

15-135-23,599-00-00

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... October 10, 1991 ... month day year

Spot N/2 - NW - SE. Sec 3... Twp 16.. S. Rg 22. X West

OPERATOR: License # 30444 Name: Charter Production Company Address: 224 E. Douglas, Suite 400 City/State/Zip: Wichita, KS 67202 Contact Person: Robert C. Spurlock Phone: 316-264-2808

2310 feet from South / West line of Section 1980 feet from East / East line of Section

IS SECTION X REGULAR IRREGULAR (NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 30606 Name: Murfin Drilling Company

County: Ness Lease Name: DINKEL Well #: 1 Field Name: Wildcat

Is this a Prorated/Spaced Field? ... yes X no Target Formation(s): Cher/Miss

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OUVO ... Disposal X Wildcat ... Cable ... Seismic; ... # of Holes ... Other

Nearest lease or unit boundary: 330' Ground Surface Elevation: 2300 feet MSL

Water well within one-quarter mile: X yes ... no Public water supply well within one mile: ... yes X no

If OUVO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Depth to bottom of fresh water: 100 Depth to bottom of usable water: 890

Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 230

Length of Conductor pipe required: N/A Projected Total Depth: 4450

Formation at Total Depth: Mississippian Water Source for Drilling Operations: well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: STATE CORPORATION COMMISSION

DNR Permit #: Will Cores Be Taken?: yes X no

If yes, proposed zone:

Exp. 2/29/92 The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

200' Alt. II Req.

RECEIVED 10-15-1991 AFFIDAVIT OCT 15 1991

1. Notify the appropriate district office prior to spudding of well:

Pusher Rodney Farr SPUD DATE 10-1-91 INIT. R.L. LENGTH SURFACE PLANNED 230 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8 @ 238 CONDUCTOR ANHYDRITE T-1776 B-1876 ELEVATION TD 4470 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ 1720 Ft. W/ SX 1 Anhydrite Base @ 1876 Ft. W/ 50 SX 2 1/2 Base Anyh. @ 950 Ft. W/ 80 SX 3 1/2, 1/2 Plug @ 500 Ft. W/ 50 SX 4 Bottom Surface @ 260 Ft. W/ 40 SX 5 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SP DATE 10-4-91 TYPE OF CEMENT 60/40/02 6 40 x 1 1/4 FS. STARTING TIME 7:15 (AM/PM) DATE 10-8-91 COMPLETION TIME 9:30 (AM/PM) DATE 10-8-91 CEMENT COMPANY Hall