

1 060795

API NUMBER 15-135-22,999-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

IRREGULAR SECTION
SE NW, SEC. 3, T 16 S, R 22 (W/X)
2970 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Victor Dinkel Well # 1

Operator: Ritchie Exploration, Inc.
Name &

County Ness 144.63

Address 125 N. Market, Suite 1000
Wichita, KS 67202

Well Total Depth 4450 Mississippi feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11:30 am Day: 3 Month: February Year: 19 86

Plugging proposal received from Mort Sherfick

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1765-1805'
Elevation 2410'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None 0

Operations Completed: Hour: 11:30 pm Day: 3 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1805' with 50 sx cement, 2nd plug at 1100' with 80
sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 11 1986
INV. NO. 12546
2-3

RECEIVED
STATE CORPORATION COMMISSION
Paul A. Luthi
(TECHNICIAN)

FEB 10 1986
02-10-1986
CONSERVATION DIVISION

CASE MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 1/21/86
month day year

API Number IS- 135-22,999-0001
IRREGULAR SECTION
S/2 SE NW 3 16 22
(location) Sec 3 Twp 16 S. Rge 22

OPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Leah Ann Kasten
Phone 316/267-4375

2970 Ft North from Southeast Corner of Section
3300 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet.
County Ness
Lease Name Victor Dinkel Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 150 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 900 feet

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4450 feet
Projected Formation at TD Mississippi
Expected Producing Formations Cherokee sand

Surface pipe by Alternate: 1 2
Surface pipe to be set 240 feet
Conductor pipe if any required feet
Ground surface elevation est. 2412' feet MSL
This Authorization Expires 7-15-86
Approved By 1-15-86

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 1/14/86 Signature of Operator or Agent Leah Ann Kasten Title Geologist
Production string will be immediately cemented from below usable water to surface.

Move in 1-23-86 set 240' 8 3/4" No

Plugged as is
PUSHER Mort Sheerick
TD 4450 FORMATION Miss
SURFACE PIPE 8 3/8" @ 251
ANHYDRITE 1765' ELEVATION 2410
STARTING TIME & DATE 2-3-86 1:30 AM
COMPLETION TIME & DATE 2-3-86 11:30 PM

1st PLUG @ 1805' FT. W/ 50 SX
2nd PLUG @ 1100' FT. W/ 80 SX
3rd PLUG @ 300' FT. W/ 370 SX
4th PLUG @ 40-0' FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15' SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX

CEMENT COMPANY *Alfred pumped 60/40 w/ 6 1/2 gal*
TECHNICIAN *Leath saw all*
1st annby w/ 50 Plugging given
2nd Cheye Base w/ 80
3 rd 30' out bottom day 50
4th 40-0 5B 10 day
Ann 15' at
6/40 w/ 6 1/2 gal

STATE CORPORATION COMMISSION

FEB 10 1986
02-10-1984
CONSERVATION DIVISION