

1 070396

8-24-87 Page 8-24-87 186 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,156-0000  
SW SW NW, SEC. 29, T. 17 S, R. 25 W/EX  
2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name Popp Well # 1-29

Operator: Sabre Exploration, Inc.

County Ness 146 25

Name &

Address 127 East Second

Well Total Depth 4500 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling, Inc. License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 12:50 p.m. Day: 24 Month: 8 Year: 1987

Plugging proposal received from John Trendley

(company name) Western Kansas Drilling, Inc. (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1797-1826' Elevation 2480'

1st plug at 1820' with 50 sx cement, 2nd plug at 1000' with 90 sx cement,

3rd plug at 280' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 24 Month: 8 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1820' with 50 sx cement,

2nd plug at 1000' with 90 sx cement,

3rd plug at 280' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 27 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 3% gel 2% cc by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 9-2-87

Signed Dan Goodwin  
(TECHNICIAN)

INV. NO. 17986

SEP 17 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date AUGUST 16, 1987 month day year

API Number 15-135-23, 156-0000

OPERATOR: License # 5190 Name Sabre Exploration, Inc. Address 127 East Second City/State/Zip Wichita, Kansas, 67202 Contact Person Matthew Totten Phone (316) 264-2635

SW SW NW Sec. 29 Twp. 17 S, Rg. 25 X West 2970 Ft. from South Line of Section 4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County NEAR

CONTRACTOR: License # 9943 Name Western Kansas Drilling, Inc. City/State Hays, Kansas

Lease Name POPP Well # 1-29

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation 2480 feet MSL

Domestic well within 350 feet yes X no Municipal well within one mile yes X no

Depth to bottom of fresh water 150' Depth to bottom of usable water 1000'

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 240'

Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 4600' feet

Formation MISSISSIPPIAN

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires 2-13-88 Approved By 8-73-87

MOORE IN 8-17-87 SET 247 498

SW SW NW Sec. 29 Twp. 17 S, Rg. 25 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth (feet), plug size (SXS), and plug type (e.g., Rathole, Mousehole).

Handwritten log entries: PUSHED John Trendler, TD 4500 FORMATION M.S.S., SURFACE PIPE 8 7/8 @ 247, ANHYDRITE 1797-1825 ELEVATION 2480, STARTING TIME & DATE 8-24-87 2:45 PM, COMPLETION TIME & DATE 8-24-87 2:45 PM, 1st PLUG @ 1860 FT. W/ 15 SX, 2nd PLUG @ 1000 FT. W/ 90 SX, 3rd PLUG @ 270 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ NO SX, WATER WELL PLUGGED W/ NO SX, 60/40 W/ 300 8 7/8 CEMENT COMPANY Halliburton, TECHNICIAN Dan Saw Part

STATE COL. AUG 27 1987 CONSERVATION DIVISION Wichita, Kansas Part Dan Saw Part