

1 070506

2-3-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,208-00-00

C SE NE, SEC. 25, T 17 S, R 25 (W/E)

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Schaben Well # 1

Operator: Vincent Oil Corporation
Name & Address: 125 North Market, Suite 1110
Wichita, KS 67202

County Ness 145.93

Well Total Depth 4490 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 2 Month: 2 Year: 19 88

Plugging proposal received from Lloyd DeLett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2466'
Anhydrite 1749-70'

1st plug at 1770' with 50 sx cement, 2nd plug at 925' with 80 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4 a.m. Day: 3 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1770' with 50 sx cement,

2nd plug at 925' with 80 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

FEB 04 1988

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE 2-12-88

INV. NO. 19836

2-3-88

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date..... 1 15 88
month day year

API Number 15- 135-23, 208-00-00 East

OPERATOR: License # 5004
Name Vincent Oil Corporation
Address 125 No. Market, Suite 1110
City/State/Zip Wichita, Kansas 67202
Contact Person Julie K. Stout
Phone (316) 262-3573

C SE NE Sec. 25 Twp. 17 S, Rg. 25 X West
3300 Ft. from South Line of Section
660 Ft. from East Line of Section

CONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, Kansas 67202

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660 feet
County Ness

Well Drilled For: Well Class: Type Equipment:
X Oil Storage X Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Schaben Well # 1
Ground surface elevation applied for feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 150
Depth to bottom of usable water 925
Surface pipe by Alternate: 1 2 X

I certify that well will comply with K.S.A. 55-101, et seq., and eventually plugging hole to KCC specifications.
Date 12-30-87 Signature of Operator or Agent Richard A. Hiebsch Title Vice President

Surface pipe planned to be set 320
Conductor pipe required
Projected Total Depth 4450 feet
Formation Mississippian

For KCC Use:
Conductor Pipe Required feet Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 6-30-88 Approved By Rich 12-30-87

EFFECTIVE DATE: 1-4-88
SPUD 1-25-88

Richard A. Hiebsch
Richard A. Hiebsch

Approved By Rich 12-30-87

C SE NE Sec. 25 Twp. 17 S, Rg. 25 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep..... 1600'	or formation with..... 60 SX	feet of..... 60/40 Pozmix (6% Gels)
2nd plug @ ft. deep..... 900'	or formation with..... 80 SX	feet of..... " "
3rd plug @ ft. deep..... 400'	or formation with..... 50 SX	feet of..... " "
4th plug @ ft. deep..... 400'	or formation with..... 10 SX	feet of..... " "
5th plug @ ft. deep..... 80'	or formation with.....	feet of.....
(2) Rathole to surface minus 5 feet		(b) Mousehole to surface minus 5 feet

PUSHER Lloyd Delett

TD 4490 FORMATION MISS

SURFACE PIPE 8 5/8" @ 360'

ANHYDRITE 1749' ELEVATION 2466'

STARTING TIME & DATE 11:00 AM

COMPLETION TIME & DATE 4:00 AM 2-3-88

1st PLUG @ 1770 FT. WI 50 SX

2nd PLUG @ 925 FT. WI 80 SX

3rd PLUG @ 390 FT. WI 40 SX

4th PLUG @ 40 FT. WI 10 SX

RAT HOLE CIRCULATED WI 15 SX

MOUSE HOLE CIRCULATED WI SX

WATER WELL PLUGGED WI Hand - SX

CEMENT COMPANY 6400 67 - ALLIED

TECHNICIAN D.G.

* 913-9257 1628

RECEIVED

STATE CORPORATION COMMISSION

04 1988

CONSERVATION DIVISION

Wichita, Kansas