

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00106-00-00
Spot: CSWNESW Sec/Twnshp/Rge: 24-17S-25W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: P POTTER Well Number: 2
County: NESS Total Vertical Depth: 4440 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: 100 N. BROADWAY, STE. 970
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 9.625 feet: 252 WITH 150 SX CMT
Production: Size 5.5 feet: 4449 WITH 200 SX CMT
Liner: Size _____ feet: _____ 144.30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2001 11:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (785) 628-6101

Proposed Plugging Method: LINER FROM 4 1/2" FROM 0-4200' WITH 475 SX CMT. TOOK INJECTION RATE OF 5 1/2 BBLS A MINUTE AT 1100#. PUMPED 40 SX CMT & 300# HULLS. PUMPED 14 SX GEL THEN 35 SX CMT. PRESSURE WENT TO 2500#. STARTED WITH WATER DISPLACEMENT. PUMPED 4 BBLS AND IT SHUT OFF. PERFORATED AT 550' AND TIED BACK ONTO CASING AND PUMPED 10 SX CMT. PRESSURED TO 300#. SHUT OFF. TIED ONTO BACKSIDE OF 4 1/2" AND 5 1/2". PRESSURED RIGHT UP. TIED ONTO BACKSIDE OF 5 1/2" AND 9 5/8". PUMPED AND PRESSURED TO 500# AND HELD.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/20/2001 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4404-08, 4397-4400, 4391-93, 4413-15, 4313-18, 4304-08, 4296-4300'. WELL HAD BEEN SQUEEZED AT 219' WITH 25 SX CMT. 1071-1125' WITH 50 SX CMT. 1400' WITH 155 SX CMT. 3319-51' WITH 25 SX CMT. LINER FROM 4 1/2" FROM 0-4200' WITH 475 SX CMT. TOOK INJECTION RATE OF 5 1/2 BBLS A MINUTE AT 1100#. PUMPED 40 SX CMT & 300# HULLS. PUMPED 14 SX GEL THEN 35 SX CMT. PRESSURE WENT TO 2500#. STARTED WITH WATER DISPLACEMENT. PUMPED 4 BBLS AND IT SHUT OFF. PERFORATED AT 550' AND TIED BACK ONTO CASING AND PUMPED 10 SX CMT. PRESSURED TO 3000#. SHUT OFF. TIED ONTO BACKSIDE OF 4 1/2" AND 5 1/2". PRESSURED RIGHT UP. TIED ONTO BACKSIDE OF 5 1/2" AND 9 5/8". PUMPED AND PRESSURED TO 500# AND HELD.

INVOICED
DATE 6-27-01
INV. NO. 2001062001
RECEIVED
KANSAS CORPORATION COMMISSION
JUN 27 2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CONSERVATION DIVISION

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

JUN 25 2001

Form CP-2/3