

051305

5-16

15-135-00105-00-00

To: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

API NUMBER 15- Drilled 7/56

NE NE NE, SEC. 24, T 17 S, R 25 W/EX

4950 feet from S section line

330 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5097

Lease Name Potter Well # 1

Operator: Martin Oil Producers, Inc.

County Ness 143.00

Name &amp; Address 150 N. Main, #1010

Well Total Depth 4400 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 162

Abandoned Oil Well X Gas Well Input Well SWD Well D&amp;A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384, Ness City, KS 67560

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 5 Year: 19 90

Plugging proposal received from Stanley Stockstill

(company name) Martin Oil Producers, Inc. (phone) 316-257-2227

were: 5 1/2" at 4400' Perfs at 4352-56' Squeezed at 807'-150 sx, -840'-200 sx, 1137'-200 sx  
3120'-150 sx, Cedar Hills w/700 sx

1st plug sand back to 4380' and dump 5 sx cement on top of sand through bailer,  
 2nd plug run tubing to base Anhydrite with 30 sx cement, 3rd plug pull tubing to 900' and  
 circulate cement, 4th plug pump 175 sx cement down annulus.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 16 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of  
sand through bailer,

2nd plug ran tubing to 1688' and pumped 30 sx cement,

3rd plug pulled tubing to 900' and circulated cement,

4th plug pumped 100 sx cement down 8 5/8" X 5 1/2" annulus.

Maximum pressure 600 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-5-90 MAY 22 1990  
INV. NO. 28318 CONSERVATION DIVISION  
Wichita, KansasSigned Richard W. Lacy  
(TECHNICIAN)FORM CP-2/3  
Rev. 01-84