

1-080195

TO:

API NUMBER 15-135-21,149 2122-00-00

5-18

STATE CORPORATION COMMISSION 150'NW C-SE-NW SEC. 16, T 17 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 1870' FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1870' FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME RYAN C WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS

OPERATOR LICENSE # 6622

WELL TOTAL DEPTH 4457' <sup>144.86</sup> FEET

OPERATOR: JASON OIL COMPANY

PRODUCTION CSG: SIZE 5 1/2" FEET 4442'

NAME AND BOX 701

SURFACE CASING: SIZE 8 5/8" FEET 273'

ADDRESS RUSSELL KS 67665

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 E. BETH DR. STERLING, KS. 67579

COMPANY TO PLUG AT: HOUR: 2:00pm DAY: 18 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM GARY WINTERS

(COMPANY NAME) RICHARD McINTYRE (PHONE) 316-727-3410

WERE:SAND BOTTOM OFF TO 4385'W/5sx  
1st PLUG @1150' W/80sx CEMENT, 2nd PLUG @630' W/50sx CEMENT, 3rd PLUG @ 300' W/40sx  
4th PLUG @ 40'W/10sx

RECEIVED  
MAY 27 1998  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS  
NONE

PLUGGING PROPOSAL RECEIVED BY KEVIN D STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 4:00pm DAY: 18 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT 1st PLUG @1070'W/5sx GEL 80sx CEMENT 4sx GEL 15 BBL WATER, 2nd PLUG @ 630' W/50sx CEMENT, 3rd PLUG @ 300'W/40sx CEMENT, 4th PLUG @ 40' W/10sx, WELL CURCULATED TO SURFACE.

BOTTOM PLUG: OPEN HOLE FROM 4442'-57' SANDED BACK TO 4385'W/5sx ON TOP

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED CASING RECOVERY 1150'  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube  
(TECHNICIAN) FORM CP-2/3

INVOICED

MAY 26 1998

DATE \_\_\_\_\_

INV. NO. 50604

5-18