

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22002-00-01
Spot: CW2NENW Sec/Twnshp/Rge: 26-13S-20W
4620 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: ZIMMERMAN Well Number: 2
County: ELLIS Total Vertical Depth: 3825 feet

Operator License No.: 30635
Op Name: LIVELY, JAMES D.
Address: 715 E. COLLEGE
BLACKWELL, OK 74631

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 170 w/130 sxs cmt
Production: Size 4.5 feet: 3810 w/150 sxs cmt
Liner: Size feet:

Well Type: EOR UIC Docket No: E23342.1 Date/Time to Plug: 11/05/2001 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 170 sxs 60/40 pozmix - 10% gel - 500# hulls.
D.V. at 1436'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/05/2001 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 750' - 1500' - 2240'.
RIH with tubing to 2010' and spotted 100 sxs with 500# hulls.
Pulled up to 1000' and circulated cement with 50 sxs.
POOH. Tied onto 4 1/2" and pumped to pressure with 10 sxs.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked onto annulus and pumped 10 sxs.
Max. P.S.I. 400#. S.I.P. 400#.

THIS IS A KCC FEE FUND PLUGGING.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

RECEIVED

NOV 14 2001

KCC WICHITA

NOV 09 2001

REPLACEMENT CARD

JOHN B. COLLINS
1007 CODY, SUITE A
HAYS, KS 67601
CONTR DREILING OIL, INC. CTY ELLIS
GEOL LAWRENCE F. GRAY FIELD IRVIN

26-13-20W
C W/2 NE NW

E 2178 KB CM 6/3/80 CARD ISSUED 8/21/80 IP OIL WELL
2173 GL ARB OH 3810-3825
LANS 3478-3701 1/2 OA
API 15-051-22,002 SHAW @ 3455

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1483	+ 695
TOP		3195	-1017
HEEB		3430	-1252
TOR		3451	-1273
LKC		3472	-1294
BKC		3720	-1542
MARM		3757	-1579
ARB		3808	-1630
RTD		3825	-1647

8-5/8" 170/130sx, 4 1/2" 3810/150sx

NO DST'S
MICT - CO, (ARB OH), AC 500 GAL,
PF 1/3613, 1/3634, 1/3669, 1/3701 1/2,
1/3455, 1/3478, 1/3508, 1/3547, AC
4000 GAL, POP

INFO RELEASED: 4/30/81
WAS OIL WELL - TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS