



TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-051-21745-00-00
 Spot: CE2NENW Sec/Twnshp/Rge: 26-13S-20W
 4620 feet from S Section Line, 2970 feet from E Section Line
 Lease/Unit Name: ZIMMERMAN Well Number: 1
 County: ELLIS Total Vertical Depth: 3817 feet

Operator License No.: 101
 Op Name: KCC FEE FUND
 Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
 Surface Casing: Size 8.625 feet: 167 w/125 sxs cmt
 Production: Size 5.5 feet: 3802 w/150 sxs cmt
 Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2001 11:30 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
 Date/Time Plugging Completed: 10/11/2001 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:
 Perforated casing at 750' - 1500' - 2240'.
 Tied onto 5 1/2" and pumped to pressure with 225 sxs and 500# hulls.
 Switched onto annulus - Instant pressure.

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
 (TECHNICIAN)

RECEIVED

NOV 13 2001

KCC WICHITA

NOV 05 2001

J. B. COLLINS
1007 CODY

#1 ZIMMERMAN

26-13-20W
C E/2 NE NW

HAYS, KS 67601
CONTR DREILING OIL, INC.

CTY ELLIS

GEOL _____ FIELD IRVIN EXT (1/8 W)

E 2180 KB CM 7/31/79 CARD ISSUED 11/3/79 IP P 57 BOPD

API 15-051-21,745

LANS 3471-3698 OA, MARM 3764-66
COMMINGLED

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
SC		1484	+ 696
TOP		3192	-1012
HEEB		3428	-1248
TOR		3448	-1268
LANS		3468	-1288
B KC		3718	-1538
MARM		3758	-1578
ARB		3798	-1618
TD		3812	-1632
DDTD		3817	-1637

8-5/8" 167/125sx, 5 1/2" 3802/150sx
DST (1) 3436-3490 (TOR-LANS)/30-30-30-30, 1500' GIP, REC 70' MCO, 180' HO&GCM, SIP 918-867#, FP 61-102/122-163#
DST (2) 3594-3615 (LANS)/30-30-10, REC 10' M, SIP 20-0#, FP 20-20/20-20#
DST (3) 3657-3690 (LANS)/30-30-30-30, 1800' GIP, REC 120' GCO, 60' HO&GCM, SIP 693-653#, FP 61-81/102-144#
MICT - CO, DD TO 3817, AC 250 GAL, SET BP @ 3800, PF (MARM) 5/3764-3766, PF (LANS) 1/3698, 1/3628, 1/3503, 1/3486, 1/3471, PF (TOR) 1/3451, AC 9500 GAL, POP P 57 BOPD & 12% WTR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS